


Features

- Acrylic
- Intuitive high-clarity color touch-screen user interface
- 6 transducers and control amplifier create 3-D surround sound experience
- Under-mount/drop-in style installation
- 15-1/16" (383 mm) deep bathing well
- Available with chromatherapy [-VBC]
- Chromatherapy model is equipped with 4 lights
- User interface mounting plate is included in color CP
- 60" (1524 mm) x 30" (762 mm) x 19" (483 mm)

5' VIBRACOUSTIC BATH K-1167-VB ALSO K-1167-VBC

ADA



Codes/Standards Applicable

Specified model meets or exceeds the following:

- ADA
- ICC/ANSI A117.1
- ASME A112.19.7
- CSA B45.5/IAPMO Z124
- UL 1795
- CAN/CSA C22.2 No. 218.2

Colors/Finishes

- 0: White
- CP: Polished Chrome
- BN: Brushed Nickel
- Other: Refer to Price Book for additional colors/finishes

Specified Model

| Model | Description | Colors/Finishes | |
|------------|-------------------------------------------------|----------------------------|--------------------------------------|
| K-1167-VB | 5' VibrAcoustic bath | <input type="checkbox"/> 0 | <input type="checkbox"/> Other _____ |
| K-1167-VBC | 5' VibrAcoustic bath with chromatherapy (shown) | <input type="checkbox"/> 0 | <input type="checkbox"/> Other _____ |

Required Accessories

| | | | |
|--------|------------------------------------------------------|-----------------------------|--------------------------------------|
| K-7271 | Clearflo slotted overflow brass bath drain OR | <input type="checkbox"/> CP | <input type="checkbox"/> Other _____ |
| K-7272 | Clearflo slotted overflow bath drain – PVC pipe | <input type="checkbox"/> CP | <input type="checkbox"/> Other _____ |

Optional Accessories

| | | | | |
|---------|---------------------------------------|----------------------------|-----------------------------|--------------------------------------|
| K-531 | Under-mount kit | | <input type="checkbox"/> NA | |
| K-1491 | Pillow | <input type="checkbox"/> 0 | | <input type="checkbox"/> Other _____ |
| K-1601 | Footstop | <input type="checkbox"/> 0 | | <input type="checkbox"/> Other _____ |
| 1172315 | Vibracoustic interface mounting plate | | <input type="checkbox"/> BN | |

Product Specification

The acrylic vibracoustic bath shall be 60" (1524 mm) in length, 30" (762 mm) in width, and 19" (483 mm) in height. Bath shall feature intuitive high-clarity color touch-screen user interface and 6 transducers and control amplifier, which create 3-D surround sound experience. Bath shall be available with chromatherapy [-VBC], which is equipped with 4 lights. Bath shall be available with under-mount or drop-in style installation. Bath shall have a 15-1/16" (383 mm) deep bathing well. The user interface mounting plate shall be included in color CP. Bath shall be Kohler Model K-1167-____-____.

UNDERScore®

Technical Information

| | | | |
|-------------------------------------------------|---------------------------------------|--------------------------------------|-------|
| Fixture*: | | | |
| Bathing well: | | | |
| Basin area, bottom | 42-3/8" (1076 mm) x 20" (508 mm) | | |
| Basin area, top | 54-3/8" (1381 mm) x 24-5/16" (618 mm) | | |
| Weight | 75 lbs (34 kg) | | |
| To overflow: | | | |
| Water depth | 15-1/16" (383 mm) | | |
| Capacity | 59.8 gal (226 L) | | |
| * Approximate measurements for comparison only. | | | |
| Drop-in cut-out | | 59-1/2" (1511 mm) x 28-1/2" (724 mm) | |
| Amplifier/control: | Power per channel (rms) W | V | Hz |
| | 15 | 120 | 50/60 |

Required Electrical Service

Dedicated circuit required, protected with Class A Ground-Fault Circuit-Interrupter (GFCI) or Residual Current Device (RCD):

Amplifier/control: 120 V, 15 A, 50/60 Hz

Installation Notes

Install this product according to the installation guide.

Will comply with **ADA** when installed per Section 607 Bathtubs of the Act.

Control amplifier fits 16" (406 mm) center studs. 25' (7.6 m) cables are included.


A grounded outlet within the wall framing must be within 24" (610 mm) of the planned control amplifier.

Four access panels are required for servicing the bath.


Floor support under bath must provide for a minimum of 50 lbs/square foot (242 kg/square meter) loading.

Access Panels


30" (762 mm) L x 15" (381 mm) H Min




No change in measurement if connected with drain illustrated. (K-7272)



User Interface



Control Amplifier



1-1/2" Bath Drain

Product Diagram